Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
17	Painting to doors and windows with 2 coats of Lac Factory green paint with standard specifications after rubbing and cleaning the surface of the wood, etc., complete ..	Sqr.	..	14·66	
18	White and colour washing in 2 coats with approved chunam and colour mixed according to proper specifications and completed ..	..	..	63·14	
19	Cement pointing to basement with cement mortar (1 cement, 4 sand) after raking and watering the joints including cutting lines, etc., and subsequently watered and completed	,,	..	41·12	
20	Skirting to walls in special wards with $\frac{3}{4}$″ thick cement concrete bed (1 cement, 2 sand, 4 granite jelly) $\frac{1}{2}$″ cubes of jelly with a coat of $\frac{1}{4}$″ thick red cement to a height of 12″ for walls as per design and subsequently watering it for 3 days	R.ft.	..	381	
21	Blocking course on parapet wall of burnt bricks of approved design with drains, etc., and plastering with 2 coats of (1 : 3) lime mortar to design with coping, etc., complete ..	,,	..	257	
22	Constructing steps with burnt granite slabs of approved quarry with 6″ rise and 10″ tread the exposed surfaces 2 line dressed with fine joints, the joints to be pointed with cement plaster (1 cement, 4 sand) the steps to be placed on a 9″ thick bed of concrete (1 lime, 2 sand, 4 of jelly granite) etc., complete ..	L.S.	..	..	

M. K. RAJAM IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE DIRECTOR OF AGRICULTURE IN MYSORE, BANGALORE.

Notification dated 29th April 1940.

The last date of receipt of tenders for the purchase of plantains and pine-apples grown on the Irwin Canal Farm, Mandya, which was fixed on 1st May 1940 has been extended up to 2 P.M. on 6th May 1940 as 1st May has since been declared to be a holiday. The tenders will be opened at 3 P.M. on 6th May 1940 in the presence of as many tenderers as may choose to attend.

T. G. RAMA IYER,
Director.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Notification No. G. N. 35, dated 29th April 1940.

SUPPLY OF SAND—AUTOMATIC TELEPHONE EXTENSION.

Sealed tenders will be received in the Office of the Chief Electrical Engineer in Mysore, Bangalore, for the supply of sand up to 12 NOON on 9th May 1940 and the tenders should be superscribed "Tenders for Sand for Automatic Telephone Works to be opened at 12 NOON on 9th May 1940." Each tender must be accompanied by a deposit of Rs. 100 (Rupees one hundred) only in cash or Government Promissory Notes, as earnest money, in default of which tenders will be rejected.

Sand, coarse in texture, clean, sharp and gritty to touch and free from earth and other impurities .. .. 2,000 C.yds.